EXTERNAL	TYPE	DESCRIPTION	AREA	LENGTH	COUNT	1ST LAYER	2ND LAYER	3RD LAYER	4TH LAYER
-	CRG020	CONCRETE WALL (SIZE TBD)	12046	3400	7	CONCRETE WALL (SIZE TBD)	-	-	-
-	W48120	5/8 GYP – 2X4 WOOD - 5/8 GYP	18243	1905	18	5/8" GYP, BD OR CEMENT BACKERBOARD ON WET WALL	2X WOOD STUD W/ BATT INSULATION	5/8" GYP, BD OR CEMENT BACKERBOARD ON WET WALL	-
-	W41E2A	STAIR/BALCONY GUARDRAIL	1516	306	6	GM_Trim_Dark	GM_Trim_Dark	1/2" OSB (NO WOOD STAMPS) - SAND/PRIME/SEAL W/ CLEAR POLYURETHANE	-
-	W48120	5/8 GYP – 2X6 WOOD - 5/8 GYP	1050	90	2	5/8" GYP, BD OR CEMENT BACKERBOARD ON WET WALL	2X WOOD STUD W/ BATT INSULATION	5/8" GYP, BD OR CEMENT BACKERBOARD ON WET WALL	-
YES	E6562D	EXTERIOR – LSL STUDS	9201	749	3	BUILDING WRAP OVER 1/2" CDX SHEATHING	ENGINEERED LUMBER (SIZE/SPACING TBD)	6 MIL VAPOR BARRIER	1/2" CDX (BFT AFF) W/ 1/2" GYP, BD ABOVE
YES	E6762D	EXTERIOR – LSL STUDS – W/ FINISHED OSB	4550	200	2	BUILDING WRAP OVER 1/2" CDX SHEATHING	ENGINEERED LUMBER (SIZE/SPACING TBD)	1/2" OSB (NO WOOD STAMPS) - SAND/PRIME/SEAL W/ CLEAR POLYURETHANE	-
YES	W6562D	EXTERIOR – WOOD STUDS	11373	475	4	BUILDING WRAP OVER 1/2" CDX SHEATHING	2X WOOD STUD W/ BATT INSULATION	5/8" GYP, BD w/ VAPOR BARRIER behind	-

3/A600 QUANTITY TAKE-OFF - WALLS

TYPE MARK	TYPE	WIDTH	HEIGHT	TYPE COMMENTS	COUNT
3F3636	ALUM. STOREFRONT WINDOW W/ INSULATED GLAZING	3' - 0"	3' - 0"	MATCH RED TRIM	13
3F3636_1	SINGLE GLAZED HOLLOW METAL WINDOW	3' - 0"	3' - 0"	FRAME: PT-2	3
5F6464	ALUM. STOREFRONT WINDOW W/ INSULATED GLAZING	5' - 4"	5' - 4"	MATCH RED TRIM	1
5F6464_4	ALUM. STOREFRONT WINDOW W/ INSULATED GLAZING	5' - 4"	5' - 4"	(4) EQUAL LIGHTS – MATCH RED TRIM	2
5F_VARIES	ALUM. STOREFRONT WINDOW W/ INSULATED GLAZING	-	-	SEE ELEVATIONS FOR SIZES	4

2/A600 WINDOW SCHEDULE - SIMPLE

TYPE MARK	TYPE	WIDTH	HEIGHT	TYPE COMMENTS
3680L	HOLLOW METAL DOOR W/ SOLID CORE WOOD PANEL	3' - 0"	6' - 8"	PANEL: PT-2 – JAMB: PT-3 (BOTH SEMI-GLOSS)
3680R	HOLLOW METAL DOOR W/ SOLID CORE WOOD PANEL	3' - 0"	6' - 8"	PANEL: PT-2 – JAMB: PT-3 (BOTH SEMI-GLOSS)
3684R	HOLLOW METAL DOOR/JAMB	3' - 0"	7' - 0"	EXTERIOR GRADE – JAMB/DOOR: PT-4
G3680L	HOLLOW METAL DOOR – METAL PANEL W/ GLASS INSERT	3' - 0"	6' - 8"	PANEL: PT-2 – JAMB: PT-3 (BOTH SEMI-GLOSS) W/ TEMPERED GLAZING
G3680R	HOLLOW METAL DOOR – METAL PANEL W/ GLASS INSERT	3' - 0"	7' - 0"	PANEL: PT-2 – JAMB: PT-3 (BOTH SEMI-GLOSS) W/ TEMPERED GLAZING
G3684R	ALUM. STOREFRONT DOOR	3' - 0"	7' - 0"	MATCH RED TRIM (W/ TEMPERED GLAZING)
G4284R	ALUM. STOREFRONT DOOR	3' - 6"	7' - 0"	MATCH RED TRIM (W/ TEMPERED GLAZING)
GD120120	INSULATED GARAGE DOOR	10' - 0"	10' - 0"	EXTERIOR GRADE – JAMB/DOOR: PT-4
GGD120120	INSULATED GLASS GARAGE DOOR	10' - 0"	10' - 0"	MATCH RED TRIM (W/ TEMPERED GLAZING)

1/A600 DOOR SCHEDULE - SIMPLE

TYPE	AREA	COUNT	1ST LAYER	2ND LAYER	3RD LAYER	4TH LAYER
ASPHALT PAVEMENT	13535	3	ASPHALT PAVEMENT	-	-	-
COMPACTED BASE - INSIDE	6910	3	6" COMPACTED CRUSHED STONE	-	-	-
COMPACTED BASE - OUTSIDE	298	1	6" COMPACTED CRUSHED STONE	-	-	-
CONCRETE SLAB AT FENCED IN AREA	337	1	5" CONCRETE SLAB ON GRADE W/6x6-W1.4xW1.4-WWF (SLOPE (2%) AWAY FROM BUILDING)	-	-	-
CONCRETE SLAB – INSIDE - FLAT	864	1	5" CONCRETE SLAB ON GRADE W/6x6-W1.4xW1.4-WWF OVER VAPOR BARRIER	-	-	-
CONCRETE SLAB – INSIDE - SLOPED TO DRAIN	4317	2	5" CONCRETE SLAB ON GRADE W/6x6-W1.4xW1.4-WWF OVER VAPOR BARRIER	-	-	-
SIDEWALK	703	1	CONCRETE PAVING	-	-	-
Tds - ABOVE DROPOFF	304	1	5/8" GYP, BD @ CEILING (SEMI-GLOSS EPOXY PAINT)	TJI (SIZE/SPACING TBD) (W/ FULL CAVITY OF BATT. INSULATION)	3/4" CDX SHEATHING	CARPET OR LVL
Tds - ABOVE OFFICE	657	1	5/8" GYP, BD @ CEILING (PT-1)	TJI (SIZE/SPACING TBD) (W/ FULL CAVITY OF BATT. INSULATION)	3/4" CDX SHEATHING	CARPET OR LVL

4/A600 QUANTITY TAKE-OFF - SLABS

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International - CC BY-SA 4.0) - freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Owner: Cool Car Guys
1600 Center Ave
Janesville, WI 53546
608.531.1600

GC: Lake Country Construction Group
161 Horizon Dr
Verona, WI 53593
608.845.1398

Architect: OpeningDesign
17 S Fairchild | FL 7
Madison, WI 53703
ryan@openingdesign.com | 773.425.6456

Date	Description
12/15/2025	PROGRESS SET

SCHEDULES
COOL CAR GUYS
1600 CENTER AVE, JANESVILLE, WI 53546

A600